



Project: Merritt Biomass Facility Project

Highlights

Owner: Fengate Capital & Dalkia Canada Inc. – Managed by Iberdrola Ingenieria
Client / Contractor: Acres Construction
Contract Value: Approx. \$3 million

Work Completed: December 2014
Region: Vancouver, BC
Technology/Service: Driven H-Piles

Scope

Keller was awarded a unit rate contract for the supply, layout, fabrication and installation of 47,775 LF of steel H-piles for the new \$235 million Merritt Biomass Facility located in Merritt, BC. The piles were installed utilizing our 75 ton and 80 ton Link-Belt cranes. Every pile required at least on splice and multiple PDA tests.

Fast Facts

- 735 ea HP12 x 63 H-Piles totaling 47,775 lineal feet
- 735 ea splices utilizing H-Pile splice sleeves, utilization of local certified welders
- 23 PDA Tests

Results/Value

All work was completed ahead of schedule, under budget with no rework while achieving an exceptional safety record of zero incidents over 3,960 manhours on site through a tight construction schedule and turnover of our scope.